

GL10-8S – 6TH STREET SEWER

CONTRACT #1 – SEWER LINES:

Unit price contract to replace 892 LF of 8" gravity sewer pipe by Directional Drill and Conventional Trench including; 4 tie-in to existing sewers, provide and install 4 new manholes, 14 service reconnects, 1 terminal lamphole, and other appurtenances required to complete the sewer line replacement. 180 LF of Gravity Sewer Service Lining and 565 LF Pressure Cleaning and Video are also part of this contract.