

MARSHALL COUNTY PSD #2 – WATER SYSTEM IMPROVEMENTS

Marshall County, WV

Contract No. 1 – Water System Improvements and Office Building Addition: Unit price contract to relocate approximately 1,825 LF of 8" waterline, 127 feet of highway borings, 200 feet of horizontal directional drilling, 30 valves (new & replacement), 3 replacement fire hydrants including 6 feet of hydrant extensions, 24 end of line flushout assemblies, 14 air release assemblies, 25 meter setter replacement/relocations, 4 tie-ins to existing mains, 1 PRV vault, 1 hydroconstant booster station, 1 booster station, rehab of 1 existing booster station, rehab of the water treatment plant, office building improvements, and other work required to provide a complete operating water system.

Contract No. 2 – Water Storage Tank and Telemetry: Lump sum contract to construction one (1) water storage tank measuring 28 feet in diameter by 65 feet in height to the overflow with a nominal volume of 299,000 gallons, including fencing, sitework, access road, and appurtenances and SCADA between new tank and Lindsay Lane Booster Station (Contract #1). Also, provide and install level gauge board, float, and accessories at the existing Wood Hill Tank (32' x 50' – welded) and Lindsay Lane Tank (25' x 70' – welded).

Contract No. 3 – Supplying Water Service Meters: Unit price contract to supply water meters and reading device to the Owner.