

FR10-16W

**CONTRACT #1 – Centerville Alma Water Extension:**

Unit price contract to construct approximately 21,230 LF of 8", 19,215 LF of 6"; 4,160 LF of 4", 6,660 LF of 3", 3,020 LF of 2" waterline, 531 feet of highway borings, 1,355 feet of horizontal directional drilling, 30 valves, 14 fire hydrants, 9 flushout assemblies, 150 meters and meter settings, 2 tie-ins to existing mains, 75 gpm Booster Station; and other work required to provide a complete operating water system.

**CONTRACT #2 – Water Storage Tank:**

Lump sum contract to construct one (1) water storage tank measuring 25 feet in diameter by 33 feet in height to the overflow with a nominal volume of 122,000 gallons. Contract also includes access road and appurtenances to make a complete operating system.