

## CENTRAL BOAZ PSD - WATER SYSTEM IMPROVEMENTS

### Wood County, WV

**Contract No. 1 - WATER LINES & BOOSTER STATION:** Unit price contract to construct approximately 23,145 feet of 8", 6", and 4" waterline, 60 feet of highway borings, 34 valves, 2 flushout assemblies, 5 air release assemblies, 24 fire hydrants, making 18 tie-ins to existing mains, one (1) booster station upgrading, and other work required to provide a complete operating water system.

**Contract No. 2 - WATER STORAGE TANK:** Lump sum contract to construct one (1) water storage tank measuring 14 feet in diameter by 79 feet in height to the overflow with a nominal volume of 89,000 gallons, including fencing, sitework and appurtenances.

**Contract No. 3 - AMR WATER SERVICE METER SYSTEM:** Unit price contract to furnish a radio read AMR water service meter system. Contract includes furnishing and installing 650 meters.